

Comberlano

Heinrich Mack
"Hofbrauhaus F.H."
Kiddie

MUNCHNER HOFBRAUHAUS
by
Mack

CARNY TOWN



MUNCHNER HOFBRAUHAUS

TABLE OF CONTENTS

Specifications	3
Set-up	4-5
Operating Procedures	6
Maintenance	7
Shut-down Procedures	8
Transporting	8

CARNYTTOWN.COM

MUNCHNER HOFBRAUHAUS

DIMENSIONS

	Width	Depth	Height
Static:	72' 0"	36' 0"	30' 0"

CAPACITY

3000 Per Hour

Interior Capacity Not To Exceed 150 Persons

ELECTRICAL

Service Required: 220/240 VAC, 3 Phase

Power Required: 125 Amps

Grounding: Green Wire Via Supply Cable

MANUFACTURER

Heinrick Mack KG
Waldkirch, West Germany

MODEL

Munchner Hofbrauhaus

TYPE

BELU

SERIAL NUMBER

9655

DATE OF MANUFACTURE

1965

MUNCHNER HOFBRAUHAUS

SET-UP

- 1) Position trailers near but NOT within the assigned location.
- 2) Layout the base components within the location making sure the 'front whalebone' is set back 3' front the midway front line.
- 3) Once the base is laid out and squared, determine the high point of the ground within the location. Using a transit level the entire base. Make certain that proper blocking is used and that blocks are placed at all load bearing points.
- 4) Once the base is level assemble the #1 section of the building. Raise this section into an upright position and secure. Assemble the #2 section and raise it into place. Connect sections #1 and #2. Using the same procedures as used with sections #1 and #2, assemble and raise (one at a time) sections #3, #4, #5 and #6.
- 5) After the building sections are erected, remove the base between sections #1 and #2. Drive or pull the 'Rocking Room' trailer into this section. Position and align this trailer as required. Once this is accomplished detach and remove the truck tractor or converter dolly. Replace the base components that were temporarily removed. Un-pin and remove the trailer rear axle. Lower the trailer onto the base and secure as required.
- 6) Next remove the base between section #3 and #4. Back the 'Floor Machinery' trailer into this section. Position and align this trailer as required. Detach and remove the truck tractor. Re-install the base components that were temporarily removed.
- 7) Unload and assemble the 'Maze Room' floor between section #2 and #3.
- 8) Unload and assemble the 'Come & Go Floor' and the 'Spinning Disc' floor that attach to the 'Floor Machinery' trailer.
- 9) Unload and position the wooden floor panels between sections #4, #5 and #6.
- 10) Unload and position the 'Rolling Barrel' at the exit between sections #5 and #6.
- 11) Starting on the left (section #1) side of the building attach the lower row of front scenery panels. Once the lower row is completed, start again at section #1 and attach the middle row of scenery panels. Once these are in place again start at section #1 and attach the upper row of scenery panels.
- 12) Now raise and attach the 'Munchner Hofbrauhaus' sign. Next attach the upper perimeter lights. Make the necessary electrical connections to the sign and upper perimeter lights at this time. Raise and attach the 6 flags & poles to the front most uprights.

MUNCHNER HOFBRAUHAUS

SET-UP

cont.

- 13) Attach the decorative panels and lights that comprise the front balcony. Once this is accomplished raise and attach to the top of the balcony the 5 animated figures. Make the electrical connections to these figures at this time.
- 14) Unload and assemble the wall panels for the 'Maze Room'.
- 15) Assemble the walls, lights and overhead canvas at the entrance between sections #1 and #2. Then attach to these walls the 4 animated 'Barnyard Houses'. Make the necessary electrical connections.
- 16) Assemble the entrance and exit ramps.
- 17) Remove the tie-down supports from under the 'Rocking Room'. Attach the steps and railings that connect the 'Rocking Room' to the 'Maze Room'.
- 18) Attach the steps and railings exiting from the 'Spinning Disc' floor.
- 19) Assemble the wall panels around the 'Rolling Barrel'.
- 20) Assemble the 'Operators Booth' positioning it near the building's rear wall directly in-line with the 'Rolling Barrel'.
- 21) Unload and attach the metal panels that comprise the rear and end walls of the building.
- 22) Attach the 5 sections of canvas (vinyl) top and secure them as required.
- 23) Raise and attach the outside speaker cabinets routing their cords to the 'Operators Booth'.
- 24) Attach all interior house lights along with the battery powered emergency lights.
- 25) Make all remaining electrical connections.
- 26) Conduct an inspection of the entire structure before connecting the main power cable. Make sure all components are properly positioned and attached. And that no tools, wires, extra parts, etc. have been left out or in the way of any moving objects.
- 27) Return all tools, spare parts, etc. to their proper place.
- 28) Apply power to the main control panel. Start each moving floor, rocking room, spinning disc, rolling barrel, etc. one at a time to assure their proper operation.

MUNCHNER HOFBRAUHAUS

OPERATING PROCEDURES

- 1) A minimum of 3 persons are necessary to man this attraction. One person must be at the entrance. Another must be in the 'Operators Booth'. The third person must be at the exit to assist patrons as they exit the 'Rolling Barrel'. Additional personnel may be necessary during peak or busy hours.
- 2) Prior to opening each day, conduct an inspection of the entire attraction. Look for anything that might have worked loose, become broken or worn.
- 3) Test all moving floors, rocking room, rolling barrel, etc. to assure that each is operating properly.
- 4) The interior and outside perimeter should be free of any trash or debris that might have accumulated.
- 5) This attraction is intended for all ages. However, very small children should be accompanied by an older companion.
- 6) As the patrons walk through the attraction there is no set time limit for their participation. Some may require longer than others.
- 7) Under no circumstances should food, drinks, lit smoking material, glass containers, etc. be allowed within the attraction.
- 8) Never allow this attraction to operate without the minimum number of personnel at their assigned positions. All personnel should be watchful of any patron having difficulty within the attraction and take steps necessary to assist them. This could be in the form of personal assistance or stopping any one of the mechanical devices.
- 9) Persons that are under the influence of drugs or alcohol, without proper foot attire, of a size they could experience difficulty within the attraction or those with a disability that could cause them injury should not be allowed in this attraction.
- 10) Any patron that becomes unruly or acts in a manner that is unacceptable to the safe operation of this attraction should be warned and if necessary removed immediately.

MUNCHNER HOFBRAUHAUS

MAINTENANCE

- 1) The attraction should be kept clean, well painted and illuminated at all times.
- 2) Any machinery not operating properly should be repaired immediately.
- 3) All moving parts must be lubricated every other day using a quality multi-purpose lubricate.
- 4) Steps, walkways, handrails, etc. should be checked daily for flaws that could result in injury to the patron. Repair as needed if such a flaw is found.
- 5) All electrical cables, sockets, connectors, etc. should be inspected each time the attraction is erected for wear and/or abuse. Repair or replace as necessary.
- 6) Check all blocking and leveling devices daily to assure proper adjustment.
- 7) The sound system should be tested for proper operation and cleaned as needed.
- 8) Check all emergency lighting daily.

MUNCHNER HOFBRAUHAUS

SHUT-DOWN PROCEDURES

- 1) Make certain that all patrons have exited the attraction.
- 2) Remove all trash that may have collected inside and around the outside perimeter of the attraction.
- 3) Turn off the main power breaker.
- 4) Take tickets to the office or designated area.

TRANSPORTING TO ANOTHER SITE

- 1) Dismantle the attraction in the reverse order in which it was erected.
- 2) Upon completion disconnect and store the power lead-in cable.
- 3) Connect the 'Rocking Room' trailer via a converter dolly to the rear of the 'Floor Machinery' trailer to complete the 'doubles' configuration.
- 4) Connect truck tractors to the 3 semi-trailer loads. Check all brakes and lights for proper operation. Check all tires for proper inflation levels.
- 5) Check the location that the attraction occupied once again to assure no misplaced blocks, pins, parts, etc. have been overlooked.
- 6) Make certain that all components are in their designated position and properly secured for over the road transportation